

CROSS LAMINATED TIMBER (CLT) WALL TEST RESULTS:

NOMINAL PIPE SIZE (MM)	TIMBER DEPTH (MM)	NOMINAL PIPE WALL THICKNESS (MM)	PRODUCT CODE	PENETRATION HOLE SIZE (MM)	WALL FRL	REPORT NUMBER
PVC PLASTIC PIPE						
40	110	2.0	ALLFC40	53	-/60/60	148132
50	110	2.2	ALLFC50	66	-/60/60	148132
65	110	2.7	ALLFC65	78	-/60/60	148132
PEX PIPE						
16	110	2.3	ALLFC25	26	-/60/45	148132
20	110	2.7	ALLFC25	30	-/60/45	148132
25	110	3.2	ALLFC25	35	-/60/30	148132

Fixing: Collars tested using Tek Screw 12G x 50mm.

CROSS LAMINATED TIMBER INSTALLATION DETAILS:

